# **Standard Operating Procedure (SOP)**

## SOP for Al-Driven Quality Inspection in Manufacturing Assembly Lines

#### Purpose:

To enhance defect detection accuracy and reduce false rejections using Al-powered multi-agent systems integrating visual and textual data.

### Scope:

Applies to all manufacturing assembly lines using Al-based quality control systems.

### Responsibilities:

Al Engineering Team: Develop and maintain Al models and multi-agent architecture.

Quality Assurance (QA) Team: Provide annotated data, validate results, and oversee compliance.

Production Supervisors: Implement escalation procedures and provide feedback.

Compliance Officer: Ensure adherence to ISO and regulatory standards.

#### Procedure:

- Deploy Vision Inspection Agent to capture images and analyze for visible defects using trained CNNs (e.g., EfficientNet).
- Use Knowledge Retrieval Agent to refer to historical defect patterns and suggest root causes via Retrieval-Augmented Generation (RAG).
- Activate Supervisor Agent to handle ambiguous cases by escalating to human review with a summarized context.
- Employ Compliance Agent to cross-verify inspection results with standards like ISO/IEC 17025 and internal SOPs.
- Continuously collect feedback from human review to fine-tune anomaly detection and escalation thresholds.
- Generate weekly defect density reports with Al-recommended corrective actions for each production unit.

#### References:

ISO/IEC 17025: General requirements for the competence of testing and calibration laboratories.

Internal QC manuals and defect troubleshooting SOPs.

Machine learning documentation for CNNs and RAG implementation.

# **Revision History:**

Rev 1.0 - Al-driven inspection SOP introduced - 2025-05-13